# E2E

CSM\_E2E\_DS\_E\_12\_4

## Your Search for Proximity Sensors Starts with the World-leading Performance and Quality of the E2E

- Standard Sensors for detecting ferrous metals.
- Wide array of variations. Ideal for a variety of applications.
- Models with different frequencies are also available to prevent mutual interference.
- Superior environment resistance with standard cable made of oilresistant PVC and sensing surface made of material that resists cutting oil.
- Useful to help prevent disconnection. Cable protector provided as a standard feature.





For the most recent information on models that have been certified for safety standards, refer to your OMRON website.



Be sure to read *Safety Precautions* on page 25.

#### **Features**

#### 2-Wire Models

# Pre-wired Models with Oil-resistant Reinforced PUR Cables Added to the Lineup and Easy Differentiation with Orange Head



Differentiation from standard models: Orange Head



Oil Resistance (Insulation service life): twice or three times that of oil-resistant vinyl chloride




Cable Flexibility: approximately twice that of vinyl chloride cables



More Flexibility at -40°C

## Lineup includes models with Smartclick pre-wired connectors for fast connection.



## **UL-recognized Models Available**



# Lineup includes models with self-diagnostic output to provide notification of failures and unstable detection conditions, such as coil burnout.

• Contributes to preventive maintenance to keep the line from stopping.

# Reduced wiring, fewer resources, and low power consumption contribute to environmentalism.

- Wiring work and amount of copper wire used reduced to two thirds of that required for 3-wire models.
- Current consumption drastically reduced to less than 10% (when a DC 2-wire model is compared with a DC 3-wire model).

## **3-Wire Models**


## Wide range of ambient operating temperatures: -40°C to 85°C (M8 to M30 models)

• Suitable for low-temperature and high-temperature applications, which are troublesome for photoelectric sensors.

## Lineup includes models with flexible cable (M8 to M30 models)

• Reduced risk of disconnection in applications with moving parts.

## **E2E Guide to Selection by Purpose**



Note: Refer to Models Not Listed in this Catalog for Long Body Models, Transmission Couplers, and Power Couplers.

## **E2E Model Number Legend**

E2E-	1	2	3	4	5	6	7	-	8	9	-	10	-	(11)	-	12		(13)	1
------	---	---	---	---	---	---	---	---	---	---	---	----	---	------	---	----	--	------	---

No.	Classification	Meaning	Remarks	
1	Appearance	Х	Cylindrical (threaded)	
	Canaina diatanas	Number	Sensing distance (Unit: mm)	Example:
2	Sensing distance	R	Indication of decimal point	1R5: 1.5 mm
	Chielding	Blank	Shielded Model	
3	Shielding	М	Unshielded Model	
		В	DC 3-wire PNP open-collector output	
		С	DC 3-wire NPN open-collector output	
		D	DC 2-wire polarity/no polarity	Whether D models have
4	Power supply and output specifications	E	DC 3-wire NPN collector load built-in output	polarity is defined by num-
	specifications	F	DC 3-wire PNP collector load built-in output	ber ⑩.
	İ	Т	AC/DC 2-wire	
		Υ	AC 2-wire	
	Form of output switching el-	1	Normally open (NO)	
<b>(5)</b>	ement	2	Normally closed (NC)	
	Oscillation fraguency type	Blank	Standard frequency	Used to prevent mutual in-
<b>6</b>	Oscillation frequency type	5	Different frequency	terference.
	Salf diagnosis	Blank	No	
7	Self-diagnosis	5	Yes	
		Blank	Pre-wired Pre-wired	
8	Connection method	M1	M12-size metal connector	
		МЗ	M8-size metal connector	
		Blank	Connector Model DC 3-wire and AC 2-wire, DC 2-wire with self-diagnosis output, DC 2-wire with old pin arrangement	
		G	Connector Model DC 2-wire with IEC pin arrangement	
9	Connector specifications	J	Pre-wired Connector Model DC 3-wire and AC 2-wire, DC 2-wire with old pin arrangement	
J		GJ	Pre-wired Connector Model DC 2-wire with IEC pin arrangement	
		TJ	Pre-wired Smartclick Connector Model DC 2-wire	
		TGJ	Pre-wired Smartclick Connector Model DC 2-wire with IEC pin arrangement	
	DC 0 mins a slouite	Blank	Polarity	
10	DC 2-wire polarity	T	No polarity	
		Blank	Standard PVC cable (oil resistant)	
11)	Cable specifications	R	Flexible PVC cable (oil resistant)	
		U	Polyurethane cable (oil resistant and reinforced)	
12	New model	N	New model (Applies only to DC 2-wire pre-wired and shielded models.)	This is blank if the cable specification in number (1) is R or U.
	Standard-certified model	US	UL-recognized model (Applies to DC 2-wire pre-wired models and pre-wired connector models.)	
13	Cable length	Letter M	Cable length (Unit: m) (Applicable to Pre-wired Models and Pre- wired Connector Models.)	Example: 2M 0.3M

Note: The purpose of this model number legend is to provide understanding of the meaning of specifications from the model number. Models are not available for all combinations of code numbers.

## **Ordering Information**

## 2-Wire Models

## Shielded DC 2-wire Models with No Self-diagnostic Output [Refer to Dimensions on page 27.]



Appear- ance	Sensing distance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *2	Model
		M12 Pre-wired Smart-	PUR (increased		NO	1: +V, 4: 0 V	Н	E2E-X2D1-M1TGJ-U 0.3M
		click Connector Mod-	oil-resistant)		NC	1: +V, 2: 0 V	11	E2E-X2D2-M1TGJ-U 0.3M
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X2D1-M1TGJ 0.3M
			PUR (increased		NO			E2E-X2D1-U 2M
		Pre-wired Models	oil-resistant)		NC			E2E-X2D2-U 2M
M8	2 mm	(2 m)	PVC (oil-resistant)	Yes	NO			E2E-X2D1-N 2M
			PVC (OII-Tesistatit)		NC			E2E-X2D2-N 2M
		M12 Connector Mod-			NO	1: +V, 4: 0 V	Α	E2E-X2D1-M1G
		els			NC	1: +V, 2: 0 V	D	E2E-X2D2-M1G
		M8 Connector Models			NO	1: +V, 4: 0 V		E2E-X2D1-M3G
		Wo Connector Wodels			NC	1: +V, 2: 0 V	'	E2E-X2D2-M3G
		M12 Pre-wired Smart-	PUR (increased		NO	1: +V, 4: 0 V		E2E-X3D1-M1TGJ-U 0.3M
		click Connector Mod-	oil-resistant)		NC	1: +V, 2: 0 V	Н	E2E-X3D2-M1TGJ-U 0.3M
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X3D1-M1TGJ 0.3M
			PUR (increased		NO			E2E-X3D1-U 2M
		Pre-wired Models	oil-resistant)	Yes	NC			E2E-X3D2-U 2M
		(2 m)	5) (0 ( "		NO			E2E-X3D1-N 2M *1
M12	3 mm		PVC (oil-resistant)		NC			E2E-X3D2-N 2M
		M12 Connector Mod-			NO	1: +V, 4: 0 V	Α	E2E-X3D1-M1G *1
		els			NC	1: +V, 2: 0 V	D	E2E-X3D2-M1G
		M12 Standard Pre- wired Connector Mod- els (0.3 m)	- PVC (oil-resistant)		NO	1: +V, 4: 0 V	Α	E2E-X3D1-M1GJ 0.3M
				Yes	NC	1: +V, 2: 0 V	D	E2E-X3D2-M1GJ 0.3M
					NO	(3, 4): (+V, 0 V)	С	E2E-X3D1-M1J-T 0.3M
		0.0 (0.0)		No *3	NC	(1, 2): (+V, 0 V)	D	
		M12 Pre-wired Smart-	PUR (increased	Y. W.	NO	1: +V, 4: 0 V		E2E-X7D1-M1TGJ-U 0.3M
		click Connector Mod-	oil-resistant)	11,0	NC	1: +V, 2: 0 V	Н	E2E-X7D2-M1TGJ-U 0.3M
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X7D1-M1TGJ 0.3M
		Pre-wired Models (2 m)	PUR (increased	Yes	NO	,		E2E-X7D1-U 2M
			oil-resistant)		NC			E2E-X7D2-U 2M
					NO			E2E-X7D1-N 2M *1
M18	7 mm		PVC (oil-resistant)		NC			E2E-X7D2-N 2M
		M12 Connector Mod-		-	NO	1: +V, 4: 0 V	Α	E2E-X7D1-M1G *1
		els			NC	1: +V. 2: 0 V	D	E2E-X7D2-M1G
					NO	1: +V, 4: 0 V	Α	E2E-X7D1-M1GJ 0.3M
		M12 Standard Pre-		Yes	NC	1: +V, 2: 0 V	D	E2E-X7D2-M1GJ 0.3M
		wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NO	(3, 4): (+V, 0 V)	С	E2E-X7D1-M1J-T 0.3M
		3.0 (0.0 111)		No *3	NC	(1, 2): (+V, 0 V)	D	E2E-X7D2-M1J-T 0.3M
		M40 D	PUR (increased		NO	1: +V, 4: 0 V		E2E-X10D1-M1TGJ-U 0.3M
		M12 Pre-wired Smart- click Connector Mod-	oil-resistant)		NC	1: +V, 2: 0 V	Н	E2E-X10D2-M1TGJ-U 0.3M
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X10D1-M1TGJ 0.3M
			PUR (increased		NO	, -	-	E2E-X10D1-U 2M
		Pre-wired Models	oil-resistant)	Yes	NC			E2E-X10D2-U 2M
		(2 m)		. 00	NO			E2E-X10D1-N 2M *1
M30	10 mm		PVC (oil-resistant)		NC	-		E2E-X10D2-N 2M
	10 111111	M12 Coppostor Mad			NO	1: +V, 4: 0 V	Α	E2E-X10D1-M1G *1
		M12 Connector Mod- els			NC	1: +V, 4: 0 V	D	E2E-X10D1-M1G
					NO	1: +V, 4: 0 V	A	E2E-X10D1-M1GJ 0.3M
			9-	Yes				
				1	Nr:	1. +/ 5. 11 //	)	F2F-X1()[)2-M11(4.1 () 3M
			PVC (oil-resistant)		NC NO	1: +V, 2: 0 V (3, 4): (+V, 0 V)	D C	E2E-X10D2-M1GJ 0.3M E2E-X10D1-M1J-T 0.3M

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X □D15 (example: E2E-X3D15-N 2M).
\*2. Refer to page 22 for details.
\*3. The residual voltage for models without polarity is 5 V, so use caution concerning the connection load interface conditions (e.g., PLC ON voltage). Refer to page 26

## Shielded DC 2-Wire UL-recognized Models with No Self-diagnostic Output [Refer to Dimensions on page 27.]



Appear- ance	Sensing distance		Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *	Model			
			M12 Pre-wired Smart-			NO	1: +V, 4: 0 V	0	E2E-X2D1-M1TGJ-US 0.3M			
M8 2 n	2 mm		click Connector Models (0.3 m)			NC 1: +V, 2: 0 V		G	E2E-X2D2-M1TGJ-US 0.3M			
IVIO	M8 2 mm		Pre-wired Models (2 m)			NO			E2E-X2D1-US 2M			
			Pre-wired Models (2 III)			NC			E2E-X2D2-US 2M			
			3 mm	clic		M12 Pre-wired Smart- click Connector Models			NO	1: +V, 4: 0 V	(	E2E-X3D1-M1TGJ-US 0.3M
M12	M12 2 mm	3 mm			(0.3 m)		NC	NC	1: +V, 2: 0 V	G	E2E-X3D2-M1TGJ-US 0.3M	
WITE	3 111111		Pre-wired Models (2 m)		NO		E2E-X3D1-US 2M					
			Fie-wired Models (2 III)	PVC (oil-resistant)	Yes	NC			E2E-X3D2-US 2M			
			M12 Pre-wired Smart-	PVC (Oil-resistant)	res	NO	1: +V, 4: 0 V	G	E2E-X7D1-M1TGJ-US 0.3M			
M18	7 m		click Connector Models (0.3 m)			NC	1: +V, 2: 0 V	G	E2E-X7D2-M1TGJ-US 0.3M			
WITO	/	111	Pro wired Medala (2 m)			NO			E2E-X7D1-US 2M			
			Pre-wired Models (2 m)			NC			E2E-X7D2-US 2M			
			M12 Pre-wired Smart-			NO	1: +V, 4: 0 V	0	E2E-X10D1-M1TGJ-US 0.3M			
M30	4	0	click Connector Models (0.3 m)			NC	1: +V, 2: 0 V	G	E2E-X10D2-M1TGJ-US 0.3M			
		10 mm	10 mm	Dra wired Madala (0 m)			NO	)		E2E-X10D1-US 2M		
			Pre-wired Models (2 m)			NC			E2E-X10D2-US 2M			

<sup>\*</sup> Refer to page 22 for details.

## Unshielded DC 2-Wire Models with No Self-diagnosis Output [Refer to Dimensions on page 27.]



Appear- ance	Sensing distance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *2	Model
		Pre-wired Models (2 m)	PVC (oil-resistant)		NO			E2E-X4MD1 2M
		Fie-wired Models (2 III)	FVC (oil-resistant)		NC	<del></del>		E2E-X4MD2 2M
M8	4 mm	M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X4MD1-M1G
IVIO	4 111111	W12 Connector Woders			NC	1: +V, 2: 0 V	D	E2E-X4MD2-M1G
		M8 Connector Models			NO	1: +V, 4: 0 V		E2E-X4MD1-M3G
		Wo Connector Woders			NC	1: +V, 2: 0 V	'	E2E-X4MD2-M3G
		M12 Pre-wired Smart- click Connector Models (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X8MD1-M1TGJ 0.3M
		Pre-wired Models (2 m)	PVC (oil-resistant)		NO			E2E-X8MD1 2M *1
M12	0	Fie-wired Models (2 III)	FVC (oil-resistant)		NC	<del></del>		E2E-X8MD2 2M
IVI I Z	8 mm	M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X8MD1-M1G *1
		W12 Connector Woders			NC	1: +V, 2: 0 V	D	E2E-X8MD2-M1G
		M12 Standard Pre-	D) (O ( ''I		NO	1: +V, 4: 0 V	Α	E2E-X8MD1-M1GJ 0.3M
		wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	
		M12 Pre-wired Smart- click Connector Models (0.3m)	PVC (oil-resistant)	Yes	NO	1: +V, 4: 0 V	G	E2E-X14MD1-M1TGJ 0.3M
		Pre-wired Models (2 m)	PVC (oil-resistant)	0	NO	100		E2E-X14MD1 2M *1
Mao	4.4	Pre-wired Models (2 m)	PVC (oii-resistant)		NC	700		E2E-X14MD2 2M
M18	14 mm	M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X14MD1-M1G *1
		W12 Connector Wodels			NC	1: +V, 2: 0 V	D	E2E-X14MD2-M1G
		M12 Standard Pre-	D) (O ( ''I ' ' ' ' ' ' )		NO	1: +V, 4: 0 V	Α	E2E-X14MD1-M1GJ 0.3M
		wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	E2E-X14MD2-M1GJ 0.3M
		M12 Pre-wired Smart- click Connector Models (0.3m)	PVC (oil-resistant)	15 M	NO	1: +V, 4: 0 V	G	E2E-X20MD1-M1TGJ 0.3M
		Dre wired Medals (0)	DVC (ail regist==+)	1	NO			E2E-X20MD1 2M *1
M30	00	Pre-wired Models (2 m)	PVC (oil-resistant)		NC			E2E-X20MD2 2M
IVIOU	20 mm		1 1 2 7	1	NO	1: +V, 4: 0 V	Α	E2E-X20MD1-M1G *1
		M12 Connector Models	19		NC	1: +V, 2: 0 V	D	E2E-X20MD2-M1G
		M12 Standard Pre-	DVC (all maximizer)	1	NO	1: +V, 4: 0 V	Α	E2E-X20MD1-M1GJ 0.3M
		wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X □D15 (example: E2E-X8MD15 2M). \*2. Refer to page 22 for details.

## Unshielded DC 2-Wire UL-recognized Models with No Self-diagnostic Output [Refer to Dimensions on page 27.]



Appear- ance	Sensing distance		Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *	Model
			M12 Pre-wired Smart- click Connector Models			NO	1: +V, 4: 0 V	G	E2E-X4MD1-M1TGJ-US 0.3M
M8	4 mm		(0.3 m)			NC	1: +V, 2: 0 V	G	E2E-X4MD2-M1TGJ-US 0.3M
IVIO	4 111111	"	Pre-wired Models (2 m)			NO			E2E-X4MD1-US 2M
			Fie-wired Models (2 III)			NC			E2E-X4MD2-US 2M
			M12 Pre-wired Smart- click Connector Models			NO	1: +V, 4: 0 V	G	E2E-X8MD1-M1TGJ-US 0.3M
M12	8 mm		(0.3 m)			NC	1: +V, 2: 0 V	G	E2E-X8MD2-M1TGJ-US 0.3M
WITE	0 111111		Pre-wired Models (2 m)			NO			E2E-X8MD1-US 2M
			Fie-wired Models (2 III)	PVC (oil-resistant)	Yes	NC			E2E-X8MD2-US 2M
			M12 Pre-wired Smart-	. vo (o resistant)	165	NO	1: +V, 4: 0 V	•	E2E-X14MD1-M1TGJ-US 0.3M
M18	14 r	mm	click Connector Models (0.3 m)			NC	1: +V, 2: 0 V	G	E2E-X14MD2-M1TGJ-US 0.3M
IVITO	141		Pre-wired Models (2 m)			NO			E2E-X14MD1-US 2M
			Fie-wired Models (2 III)			NC			E2E-X14MD2-US 2M
			M12 Pre-wired Smart-			NO	1: +V, 4: 0 V	0	E2E-X20MD1-M1TGJ-US 0.3M
M30		20 mm	click Connector Models (0.3 m)			NC	1: +V, 2: 0 V	G	E2E-X20MD2-M1TGJ-US 0.3M
IVIOO	IVIOU	20 111111	Pre-wired Models (2 m)			NO			E2E-X20MD1-US 2M
			Fie-wired Models (2 III)			NC			E2E-X20MD2-US 2M

<sup>\*</sup> Refer to page 22 for details.

## Shielded DC 2-Wire Models with Self-diagnosis Output [Refer to Dimensions on page 27.]



Appear- ance	Sensing distance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *2	Model
		Pre-wired Models (2 m)	PVC (oil-resistant)	Jahra.				E2E-X3D1S 2M *1
M12	3 mm	M12 Connector Models	- A			2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X3D1S-M1
		Pre-wired Models (2 m)	PVC (oil-resistant)					E2E-X7D1S 2M *1
M18	7 mm	M12 Connector Models		Yes		2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X7D1S-M1
		Pre-wired Models (2 m)	PVC (oil-resistant)					E2E-X10D1S 2M *1
M30	10 mm	M12 Connector Models				2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X10D1S-M1

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X □D15S (example: E2E-X3D15S 2M). \*2. Refer to page 22 for details.

#### Unshielded DC 2-Wire Models with Self-diagnosis Output [Refer to Dimensions on page 27.]




Appear- ance	Sensing distance		Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *2	Model		
			Pre-wired Mod- els (2 m)	PVC (oil-resistant)					E2E-X8MD1S 2M *1		
M12	8 mm		M12 Connector Models						2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X8MD1S-M1
			Pre-wired Mod- els (2 m)	PVC (oil-resistant)					E2E-X14MD1S 2M *1		
M18	14	mm	M12 Connector Models		Yes	NO	2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X14MD1S-M1		
			Pre-wired Mod- els (2 m)	PVC (oil-resistant)					E2E-X20MD1S 2M *1		
M30		20 mm	M12 Connector Models				2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X20MD1S-M1		

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X \( \sum MD15S \) (example: E2E-X8MD15S 2M).

#### **Connector Pin Assignments of DC 2-Wire Models**

- The connector pin assignments of each New E2E DC 2-Wire Model conform to IEC 947-5-2 Table III. (Only DC 2-Wire Models have been changed in comparison to the previous models.)
- The following models with conventional connector pin assignments are available as well. (Only NO Models can be used.)
   The cable at the right should also be used if the XW3D-P□55-G11/ XW3B-P□55-G11 Connector Junction Box is already being used.

Cable length	Model
500 mm	XS2W-D421-BY1



## Models with conventional connector pin assignments are available as well.

Annoore	naa	Model									
Appeara	ince	NO	Applicable connector code *	NC	Applicable connector code *						
	M8	E2E-X2D1-M1	С	E2E-X2D2-M1	D						
Shielded	M12	E2E-X3D1-M1	С	E2E-X3D2-M1	D						
	M18	E2E-X7D1-M1	С	E2E-X7D2-M1	D						
	M30	E2E-X10D1-M1	С	E2E-X10D2-M1	D						
	M8	E2E-X4MD1-M1	С	E2E-X4MD2-M1	D						
Unshielded	M12	E2E-X8MD1-M1	С	E2E-X8MD2-M1	D						
	M18	E2E-X14MD1-M1	С	E2E-X14MD2-M1	D						
	M30	E2E-X20MD1-M1	С	E2E-X20MD2-M1	D						

<sup>\*</sup> Refer to page 22 for details.

<sup>\*2.</sup> Refer to page 22 for details.

## AC 2-Wire Models Shielded Models [Refer to Dimensions on page 27.]



Appear- ance	Sensing distance		Connection method	Cable specifications	Operation mode	Pin arrangement	Applicable con- nector code *2	Model	
M8	<b>1</b> 4 5		Pre-wired Models	PVC (oil-resistant)	NO			E2E-X1R5Y1 2M	
IVIO	1.5 m	m	(2 m)	F VC (OII-Tesistatit)	NC			E2E-X1R5Y2 2M	
			Pre-wired Models	PVC (oil-resistant)	NO			E2E-X2Y1 2M *1	
M12		2 mm	(2 m)	F VC (OII-Tesistatit)	NC			E2E-X2Y2 2M	
IVIIZ	2 mm		M12 Connector		M12 Connector		NO	(3, 4): (AC, AC)	E
			Models		NC	(1, 2): (AC, AC)	F	E2E-X2Y2-M1	
			Pre-wired Models (2 m) M12 Connector	PVC (oil-resistant)	NO			E2E-X5Y1 2M *1	
M18	5 m			r vo (oii-resistarit)	NC			E2E-X5Y2 2M	
WITO	511				NO	(3, 4): (AC, AC)	E	E2E-X5Y1-M1	
			Models		NC	(1, 2): (AC, AC)	F	E2E-X5Y2-M1	
			Pre-wired Models	PVC (oil-resistant)	NO			E2E-X10Y1 2M *1	
M30	M30 1	10 mm	(2 m)	r vo (oii-resistarit)	NC	]		E2E-X10Y2 2M	
IVIOU		10 mm	M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X10Y1-M1	
			Models		NC	(1, 2): (AC, AC)	F	E2E-X10Y2-M1	

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X  $\Box$ Y $\Box$ 5 (example: E2E-X5Y15 2M).

#### **Unshielded Models**



Appear- ance	Sensing distance		Connection method	Cable specifications	Operation mode	Pin arrangement	Applicable con- nector code *2	Model					
M8	<b>-</b>			Pre-wired Models	PVC (oil-resistant)	NO	" KJ 11 2.		E2E-X2MY1 2M				
IVIO	2 mm	<b>1</b>		(2 m)	PVC (oii-resistant)	NC	\$3 EQ.		E2E-X2MY2 2M				
				Pre-wired Models	PVC (oil-resistant)	NO	A.		E2E-X5MY1 2M *1				
M12	2 5 mm			(2 m)	PVC (OII-resistant)	NC			E2E-X5MY2 2M				
IVI I Z	5 III	13 11111		M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X5MY1 2M				
				Models	75	NC	(1, 2): (AC, AC)	F	E2E-X5MY2-M1				
					Pre-wired Models	DVC (oil registant)	NO			E2E-X10MY1 2M *1			
M18	40.			10 mm	10 mm	(2	(2 m)	PVC (oil-resistant)	NC			E2E-X10MY2 2M	
IVITO		10 mm	10 mm			10 mm	10 mm	10 mm		M12 Connector		NO	(3, 4): (AC, AC)
				Models		NC	(1, 2): (AC, AC)	F	E2E-X10MY2-M1				
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X18MY1 2M *1				
M30	M30		18 mm	(2 m)	i vo (oii-lesistalit)	NC	- <b></b>		E2E-X18MY2 2M				
IVIOU			10 111111	M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X18MY1-M1				
				Models	-22	NC	(1, 2): (AC, AC)	F	E2E-X18MY2-M1				

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X □MY□5 (example: E2E-X5MY15 2M). \*2. Refer to page 22 for details.

## AC 2-Wire Models Shielded Models [Refer to Dimensions on page 27.] (There are no unshielded models.)



Appear- ance	Sensing distance	Connection method	Cable specifications	Operation mode	Pin arrangement	Applicable connector code	Model
M12	3 mm	Pre-wired Models (2 m)	PVC (oil-resis- tant)				E2E-X3T1 2M
M18	7 mm	Pre-wired Models (2 m)	PVC (oil-resis- tant)	NO			E2E-X7T1 2M
M30	10 mm	Pre-wired Models (2 m)	PVC (oil-resistant)				E2E-X10T1 2M

<sup>\*2.</sup> Refer to page 22 for details.

## Shielded DC 3-Wire Models [Refer to *Dimensions* on page 27.]



				0.11			Appli-	Mo	odel
Appear- ance	Sensing dista	ance	Connection method	Cable specifica-tions	Opera- tion mode	Pin arrangement	cable connec- torcode *2	NPN output	PNP output
		Pre-wire		PVC (oil-re- sistant)	NO			E2E-X1R5E1 2M	E2E-X1R5F1 2M
			(2 m)	PVC (oil-re- sistant)	NC			E2E-X1R5E2 2M	E2E-X1R5F2 2M
M8	4.5		M12 Connector Models		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X1R5E1-M1	E2E-X1R5F1-M1
M8 1.5 mm	1.5 mm				NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X1R5E2-M1	E2E-X1R5F2-M1
			M8 Connector		NO	1: +V, 3: 0 V, 4: Control output	- 1	E2E-X1R5E1-M3	E2E-X1R5F1-M3
		Models	Models		NC	1: +V, 3: 0 V, 2: Control output		E2E-X1R5E2-M3	E2E-X1R5F2-M3
		M12 Connector	Pre-wired Models	PVC (oil-re-	NO			E2E-X2E1 2M *1	E2E-X2F1 2M *1
			sistant)	NC			E2E-X2E2 2M	E2E-X2F2 2M	
M12	2 mm				NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X2E1-M1	E2E-X2F1-M1
			Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X2E2-M1	E2E-X2F2-M1
			Pre-wired Models	PVC (oil-re-	NO			E2E-X5E1 2M *1	E2E-X5F1 2M *1
			(2 m)	sistant)	NC	7	<b>#</b>	E2E-X5E2 2M	E2E-X5F2 2M
M18	5 mm		M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X5E1-M1	E2E-X5F1-M1
			Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X5E2-M1	E2E-X5F2-M1
			Pre-wired Models	PVC (oil-re-	NO	L. X.	The second	E2E-X10E1 2M *1	E2E-X10F1 2M
			(2 m)	sistant)	NC	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		E2E-X10E2 2M	E2E-X10F2 2M
M30	M30 10 mm		M12 Connector	Connector		1: +V, 3: 0 V, 4: Control output	В	E2E-X10E1-M1	E2E-X10F1-M1
			Models	n m	NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X10E2-M1	E2E-X10F2-M1

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X□□□5 (example: E2E-X5E15 2M). \*2. Refer to page 22 for details.

## Unshielded DC 3-Wire Models [Refer to *Dimensions* on page 27.]



					0		Appli-	Mo	del
Appear- ance	Sensing dis	stance	Connection method	Cable specifications	Opera- tion mode	Pin arrangement	cable connec- torcode *2	NPN output	PNP output
			Pre-wired Models	PVC (oil-resis-	NO			E2E-X2ME1 2M	E2E-X2MF1 2M
			(2 m)	tant)	NC			E2E-X2ME2 2M	E2E-X2MF2 2M
			M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X2ME1-M1	E2E-X2MF1-M1
M8	2 mm		Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X2ME2-M1	E2E-X2MF2-M1
			M8 Connector		NO	1: +V, 3: 0 V, 4: Control output		E2E-X2ME1-M3	E2E-X2MF1-M3
			Models		NC	1: +V, 3: 0 V, 2: Control output	'	E2E-X2ME2-M3	E2E-X2MF2-M3
			Pre-wired Models	PVC (oil-resis-	NO			E2E-X5ME1 2M *1	E2E-X5MF1 2M
			(2 m)	tant)	NC			E2E-X5ME2 2M	E2E-X5MF2 2M
M12	5 mm		M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X5ME1-M1	E2E-X5MF1-M1
			Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X5ME2-M1	E2E-X5MF2-M1
			Pre-wired Models	PVC (oil-resis-	NO			E2E-X10ME1 2M *1	E2E-X10MF1 2M
			(2 m)	tant)	NC			E2E-X10ME2 2M	E2E-X10MF2 2M
M18	10 mm		M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X10ME1-M1	E2E-X10MF1-M1
			Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X10ME2-M1	E2E-X10MF2-M1
			Pre-wired Models	PVC (oil-resis-	NO	V. Mari	J	E2E-X18ME1 2M *1	E2E-X18MF1 2M
				NC	A KANTED		E2E-X18ME2 2M	E2E-X18MF2 2M	
M30		18 mm	M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X18ME1-M1	E2E-X18MF1-M1
			Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X18ME2-M1	E2E-X18MF2-M1

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X□M□□5 (example: E2E-X5ME15 2M). \*2. Refer to page 22 for details. CU AT

## **Ratings and Specifications**

#### **E2E-X**DD DC 2-Wire Models

	Size	N	Л8	M	112	M	118	M30			
	Shielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded		
Item	Model	E2E-X2D□	E2E-X4MD□	E2E-X3D□	E2E-X8MD□	E2E-X7D□	E2E-X14MD□	E2E-X10D	E2E-X20MD□		
Sensing	distance	2 mm ±10%	4 mm ±10%	3 mm ±10%	8 mm ±10%	7 mm ±10%	14 mm ±10%	10 mm ±10%	20 mm ±10%		
Set dist	ance *1	0 to 1.6 mm	0 to 3.2 mm	0 to 2.4 mm	0 to 6.4 mm	0 to 5.6 mm	0 to 11.2 mm	0 to 8 mm	0 to 16 mm		
Differen	tial travel	15% max. of se	nsing distance	10% max. of ser	nsing distance	1	1	1			
Detecta	ble object	Ferrous metal (*	The sensing dista	nce decreases wi	th non-ferrous me	tal. Refer to Engi	neering Data on p	pages 17 and 18.			
Standar object	d sensing	Iron, 8 × 8 × 1 mm	Iron, 20 × 20 × 1 mm	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$							
Response frequency *2		1.5 kHz	1 kHz	1	0.8 kHz	0.5 kHz	0.4 kHz		0.1 kHz		
	upply voltage ng voltage	Standard Models: 12 to 24 VDC, ripple (p-p): 10% max. (10 to 30 VDC) US Models and Connector Models Used as UL-certified Models: 12 to 24 VDC, ripple (p-p): 10% max. (The operating voltage range is also the same.) *3									
Leakage	current	0.8 mA max.	<u>-</u>					•			
	Load current	3 to 100 mA, Di	agnostic output: 5	0 mA for -D1(5)S	Models						
Control output	Residual voltage *4	3 V max. (Load current: 100 mA, Cable length: 2 m, M1J-T Models only: 5 V max.)									
Indicato	ors		eration indicator (r eration indicator (r	red) and setting in red)	dicator (green)						
	on mode nsing object ching)	D1 Models: NO D2 Models: NC	Refer to the ti	iming charts unde	r I/O Circuit Diagi	rams on page 20 t	for details.				
Diagnostic output delay 0.3 to 1 s											
Protecti	on circuits	Surge suppress	or, Load short-cire	cuit protection (for	r control and diag	nostic output)	7.				
Ambien tempera	t iture range	Operating: -25	to 70°C, Storage:	-40 to 85°C (with	no icing or conde	ensation)	·				
Ambien humidit		Operating/stora	ge: 35% to 95% (v	with no condensa	tion)	& KOHI					
Tempera influence		±15% max. of sensing distance at 23°C in the temperature range of –25 to 70°C   ±10% max. of sensing distance at 23°C in the temperature range of –25 to 70°C									
Voltage	influence	$\pm 1\%$ max. of sensing distance at rated voltage in the rated voltage $\pm 15\%$ range									
Insulatio	on resistance	50 MΩ min. (at 500 VDC) between current-carrying parts and case									
Dielectr	ic strength	1000 VAC, 50/60 Hz for 1 minute between current carry parts and case									
Vibratio	n resistance	Destruction: 10	to 55 Hz, 1.5-mm	double amplitude	for 2 hours each	in X, Y, and Z dir	ections				
Shock r	esistance	Destruction: 500 10 times each in Z directions		Destruction: 1,0	00 m/s <sup>2</sup> 10 times	each in X, Y, and	`				
Degree	of protection		ls: IEC 60529 IP6 els: IEC 60529 IP	67, in-house stand 67	lards: oil-resistant	:					
Connec	tion method	Pre-wired Mode	ls (Standard cable	e length: 2 m), Co	nnector Models,	or Pre-wired Conr	nector Models (St	andard cable leng	gth: 0.3 m)		
	Pre-wired Models	Approx. 60 g		Approx. 70 g		Approx. 130 g		Approx. 175 g			
Weight (pack- ed state)	Pre-wired Connector Models	-		Approx. 40 g		Approx. 70 g		Approx. 110 g			
	Connector Models	Approx. 15 g		Approx. 25 g		Approx. 40 g		Approx. 90 g			
	Case	Stainless steel (	SUS303)	Nickel-plated br	ass						
Matari	Sensing sur- face	РВТ		-							
Materi- als	Clamping nuts	Nickel-plated br	ass								
	Toothed washer	Zinc-plated iron									
Accesso	ories	Instruction man	ual								
		•									

<sup>\*1.</sup> Use the E2E within the range in which the setting indicator (green LED) is ON (except D2 Models).

The response frequency is an average value.
 The response frequency is an average value.
 Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.
 For the information on UL-certified connector models, refer to your OMRON website.
 The residual voltage of each M1J-T Model is 5 V. When connecting to a device, make sure that the device can withstand the residual voltage. (Refer to page 26 for details.)

## **E2E-X**□**Y**□ **AC 2-Wire Models**

	Size	N	Л8	N	W12	IV	118		M30			
	Shielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded			
Item	Model	E2E-X1R5Y	E2E-X2MY□	E2E-X2Y□	E2E-X5MY	E2E-X5Y□	E2E-X10MY	E2E-X10Y	E2E-X18MY			
Sensing d	listance	1.5 mm ±10%	2 mm ±10%	II.	5 mm ±10%		10 mm ±10%		18 mm ±10%			
Set distan	nce	0 to 1.2 mm	0 to 1.6 mm		0 to 4 mm		0 to 8 mm		0 to 14 mm			
Differentia	al travel	10% max. of ser	nsing distance									
Detectable				nce decreases w	vith non-ferrous me	tal Refer to <i>Engi</i>	neering Data on r	page 18 )				
Standard object	•	Iron, 8 × 8 × 1 mm	Iron, 12 × 12 ×		Iron, 15 × 15 × 1 mm	Iron,	Iron 20 × 20 × 3	,	Iron, 54 × 54 × 1 m			
	frequency	25 Hz	1			1						
	pply voltage	24 to 240 VAC (20 to 264 VAC), 50/60 Hz										
Leakage o	current	1.7 mA max.	7 mA max.									
Control	Load current *2	5 to 100 mA		5 to 200 mA		5 to 300 mA						
output	Residual voltage	Refer to Engineering Data on page 19.										
ndicators	3	Operation indica	ator (red)									
Operation (with sens approachi	sing object	Y1 Models: NO Y2 Models: NC	Refer to the ti	ming charts unde	er I/O Circuit Diagr	ams on page 21 f	or details.					
Protection	n circuits	Surge suppressor										
Ambient t ange *1*2	emperature 2	Operating/Stora (with no icing or		Operating/Stora	age: -40 to 85°C (	with no icing or co	ondensation)					
Ambient humidity i	range	Operating/storag	ge: 35% to 95% (	with no condensa	ation)	a TV	1					
Temperati influence	ure	±10% max. of sensing distance at 23°C in the temperature range of –40 to 85°C, ±10% max. of sensing distance at 23°C in the temperature range of –40 to 85°C, ±10% max. of sensing distance at 23°C in the temperature range of –25 to 70°C										
Voltage in	fluence	±1% max. of sensing distance at rated voltage in the rated voltage ±15% range										
nsulation	resistance	50 MΩ min. (at 500 VDC) between current-carrying parts and case										
Dielectric	strength	4,000 VAC (M8 Models: 2,000 VAC), 50/60 Hz for 1 min between current-carrying parts and case										
Vibration	resistance	Destruction: 10 to 55 Hz, 1.5-mm double amplitude for 2 hours each in X, Y, and Z directions										
Shock res	sistance	Destruction: 500 m/s <sup>2</sup> 10 times each in X, Y, and Z directions  Destruction: 1,000 m/s <sup>2</sup> 10 times each in X, Y, and Z directions										
Degree of	protection	Pre-wired Models: IEC 60529 IP67, in-house standards: oil-resistant Connector Models: IEC 60529 IP67										
Connectio	on method	Pre-wired Mode	ls (Standard cabl	e length: 2 m) an	d Connector Mode	els						
Weight packed	Pre- wired Models Model	Approx. 60 g		Approx. 70 g		Approx. 130 g		Approx. 175 g				
state)	Connec- tor Models	Approx. 15 g		Approx. 25 g		Approx. 40 g		Approx. 90 g				
	Case	Stainless steel (	SUS303)	Nickel-plated b	rass	1		1				
	Sensing surface	РВТ	<u> </u>	· ·								
Materials	Clamp- ing nuts	Nickel-plated bra	ass									
	Toothed washer	Zinc-plated iron										
Accessori	ies	Instruction manu	ual									

<sup>\*1.</sup> When supplying 24 VAC to any of the above models, make sure that the operating ambient temperature range is at least -25°C.
\*2. When using an M18 or M30 Connector Model at an ambient temperature between 70 and 85°C, make sure that the Sensor has a control output (load current) of 5 to 200 mA max.

## **E2E-X**T1 AC/DC 2-Wire Models

	Size	M12	M18	M30						
	Shielded		Shielded							
Item	Model	E2E-X3T1	E2E-X7T1	E2E-X10T1						
Sensing dista	nce	3 mm ±10%	7 mm ±10%	10 mm ±10%						
Set distance		0 to 2.4 mm	0 to 5.6 mm	0 to 8 mm						
Differential tra	ivel	10% max. of sensing distance								
Detectable ob	ject	Ferrous metal (The sensing distance	decreases with non-ferrous metal.	Refer to Engineering Data on page 17.)						
Standard sens	sing object	Iron, 12 × 12 × 1 mm	Iron, 18 × 18 × 1 mm	Iron, 30 × 30 × 1 mm						
Response	DC	1 kHz	0.5 kHz	0.4 kHz						
frequency *1	AC	25 Hz								
Power supply (operating vol	voltage tage range) *2	24 to 240 VDC (20 to 264 VDC) 48 to 240 VAC (40 to 264 VAC)								
Leakage curre	ent	DC: 1 mA max. AC: 2 mA max.								
Control	Load current	5 to 100 mA								
output	Residual voltage	DC: 6 V max. (Load current: 100 mA, Cable length: 2 m) AC: 10 V max. (Load current: 5 mA, Cable length: 2 m)								
Indicators		Operation indicator (red), Setting ind	Operation indicator (red), Setting indicator (green)							
Operation mo (with sensing approaching)		NO (Refer to the timing charts under	1/O Circuit Diagrams on page 21 for de	etails.)						
Protection circ	cuits	Load short-circuit protection (20 to 4	0 VDC only), Surge suppressor							
Ambient temp	erature range	Operating: -25 to 70°C, Storage: -40 to 85°C (with no icing or condensation)								
Ambient humi	dity range	Operating/Storage: 35% to 95% (with no condensation)								
Temperature i	nfluence	±10% max. of sensing distance at 23°C in the temperature range of –25 to 70°C								
Voltage influe	nce	$\pm 1\%$ max. of sensing distance at rated voltage in the rated voltage $\pm 15\%$ range								
Insulation res	istance	50 MΩ min. (at 500 VDC) between current-carrying parts and case								
Dielectric stre	ngth	4,000 VAC, 50/60 Hz for 1 minute be	etween current-carrying parts and c	ase						
Vibration resis	stance	Destruction: 10 to 55 Hz, 1.5-mm do	uble amplitude for 2 hours each in	X, Y, and Z directions						
Shock resista	nce	Destruction: 1,000 m/s <sup>2</sup> 10 times each	ch in X, Y, and Z directions							
Degree of pro	tection	IEC 60529 IP67, in-house standards	: oil-resistant							
Connection m	ethod	Pre-wired Models (Standard cable le	ength: 2 m)							
Weight (packe	ed state)	Approx. 80 g	Approx. 140 g	Approx. 190 g						
	Case	Nickel-plated brass								
	Sensing surface	РВТ								
Materials	Clamping nuts	Nickel-plated brass								
	Toothed washer	Zinc-plated iron								
Accessories		Instruction manual								
		I.								

<sup>\*1.</sup> The response frequency is an average value. Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.

\*2. Power Supply Voltage Waveform:
Use a sine wave for the power supply. Using a rectangular AC power supply may result in faulty reset.

#### **E2E-X**| E | F | DC 3-Wire Models

	Size		M8	N	/l12	М	18	M30				
	Shielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded			
Item	Model	E2E -X1R5E□/F□	E2E -X2ME□/F□	E2E -X2E□/F□	E2E -X5ME□/F□	E2E -X5E□/F□	E2E -X10ME□/F□	E2E-X10E□/ F□	E2E -X18ME□/F□			
Sensing di	istance	1.5 mm ±10%	2 mm ±10%		5 mm ±10%		10 mm ±10%		18 mm ±10%			
Set distand	се	0 to 1.2 mm	0 to 1.6 mm		0 to 4 mm		0 to 8 mm		0 to 14 mm			
Differentia	l travel	10% max. of se	nsing distance									
Detectable	object	Ferrous metal (	The sensing dista	nce decreases w	ith non-ferrous me	tal. Refer to <i>Engii</i>	neering Data on p	page 18.)				
Standard s object	sensing	Iron, $8 \times 8 \times 1 \text{ mm}$	Iron, 12 × 12 × 1 mm		Iron, 15 ×15 × 1 mm	Iron, 18 × 18 × 1 mm	Iron, $30 \times 30 \times 1 \text{ mm}$		Iron, 54 × 54 × 1 mm			
Response 1	frequency	2 kHz	0.8 kHz	1.5 kHz	0.4 kHz	0.6 kHz	0.2 kHz	0.4 kHz	0.1 kHz			
Power sup (operating range) *2	ply voltage voltage	12 to 24 VDC, ripple(p-p): 10% max. (10 to 30 VDC) Connector Models Used as UL-certified Models: 12 to 24 VDC, ripple (p-p): 10% max. (The operating voltage range is also the same.) *3										
Current co	nsumption	13 mA max.										
	Load current *2	200 mA max.										
	Residual voltage	2 V max. (Load	/ max. (Load current: 200 mA, Cable length: 2 m)									
Indicators		Operation indica	ator (red)									
Operation (with sensi approachir	ing object	E1/F1 Models: I E2/F2 Models: I Refer to the time	NC	O Circuit Diagran	ns on page 21 for	details.						
Protection	circuits	Load short-circu	uit protection, Sur	ge suppressor, R	everse polarity pro	tection	0					
Ambient temperature range *2 Operating/Storage: -40 to 85°C (with no icing or condensation)												
Ambient hi	umidity	Operating/Stora	age: 35% to 95% (	with no condensa	ation)	N. Proj	b.					
Temperatu influence	ire				perature range of perature range of							
Voltage inf	fluence	$\pm 1\%$ max. of sensing distance at rated voltage in the rated voltage $\pm 15\%$ range										
Insulation	resistance	50 M $\Omega$ min. (at 500 VDC) between current-carrying parts and case										
Dielectric s	strength	1,000 VAC, 50/60 Hz for 1 minute between current carry parts and case										
Vibration r	esistance	Destruction: 10 to 55 Hz, 1.5-mm double amplitude for 2 hours each in X, Y, and Z directions										
Shock resi	istance	Destruction: 500 10 times each in Z directions		Destruction: 1,0	000 m/s <sup>2</sup> 10 times	each in X, Y, and	Z directions					
Degree of	protection	Pre-wired Mode Connector Mode	els : IEC 60529 IF els : IEC 60529 IF	P67, in-house star P67	ndards: oil-resistar	nt						
Connection	n method	Pre-wired Mode	els (Standard cabl	e length: 2 m) an	d Connector Mode	ls						
Weight	Pre- wired Models	Approx. 65 g		Approx. 75 g		Approx. 150 g		Approx. 195 g				
(packed state)	Connector Models	Approx. 15 g		Approx. 25 g		Approx. 40 g		Approx. 90 g				
	Case	Stainless steel (	(SUS303)	Nickel-plated b	rass	I.		I				
	Sensing surface	PBT		1								
Materials	Clamp- ing nuts	Nickel-plated br	ass									
	Toothed washer	Zinc-plated iron										
Accessorie	es	Instruction man	ual									


<sup>\*1.</sup> The response frequency is an average value. Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.
\*2. When using an M8 Model at an ambient temperature between 70 and 85°C, supply 10 to 30 VDC to the Sensor and make sure that the Sensor has a control output of 100 mA maximum.
\*3. For the information on UL-certified connector models, refer to your OMRON website.

## **Engineering Data (Reference Value)**


## **Sensing Area**

#### **Shielded Models**

#### E2E-X D /-X T1





#### $E2E-X\Box E\Box /-X\Box Y\Box /-X\Box F\Box$




## **Unshielded Models**

#### E2E-X MD









#### **Influence of Sensing Object Size and Material**


#### E2E-X2D




## E2E-X3D\(\to\)/-X3T1




E2E-X7D\\(\text{/-X7T1}\)




## E2E-X10D /-X10T1




E2E-X4MD




E2E-X8MD




#### E2E-X14MD




#### E2E-X20MD




#### **E2E-X1R5E** /- **X1R5Y** /- **X1R5F**




## E2E-X2E /- X2Y /- X2F




**E2E-X5E** /- **X5Y** /- **X5F** 




**E2E-X10E** /- **X10Y** /- **X10F** 




#### E2E-X2ME /-X2MY /-X2MF




E2E-X5ME /-X5MY /-X5MF




**E2E-X10ME** /-**X10MY** /-**X10MF** 





#### **E2E-X18ME** /- **X18MY** /- **X18MF**




## **Leakage Current**











## **Residual Output Voltage**











## I/O Circuit Diagrams

## **E2E-X**□**D**□ **DC 2-Wire Models**

Operation mode	Model	Timing Chart	Output circuit
Without self-	E2E-X□D1-N E2E-X□D1-M1G(J) E2E-X□D1(-M1TGJ)-U E2E-X□D1-M3G E2E-X□D1(-M1TGJ)-US	Non-sensing area area Sensing Stable sensing area  Sensing Object Proximity Sensor	Polarity: Yes  Prox Load How L
diagnostic output: NO	E2E-X□D1-M1J-T	Rated sensing distance  OFF (green)  ON Operation on o	Polarity: None  Polarity: None  (0 V)  Note 1. The load can be connected to either the +V or 0 V side.  2. The E2E-X□D1-M1J-T has no polarity. Therefore, terminals 3 and 4 have no polarity.
Without self- diagnostic output: NC	E2E-X□D2-N E2E-X□D2-M1G E2E-X□D2(-M1TGJ)-U E2E-X□D2-M3G E2E-X□D2(-M1TGJ)-US	Non-sensing area  Sensing object  (%) 100 0  Rated sensing distance  ON Operation indicator (red) ON OFF  Control output	Prox- imity Brown  Note: The load can be connected to either the +V or 0 V side.
With self- diagnostic output: NO	E2E-X□D1S E2E-X□D1S-M1	Vinstable sensing area  Sensing object  Sensing object  Sensing object  Sensing object  Sensing object  OFF Setting indicator (green)  OFF Control output  ON  OFF Diagnostic output*  * The diagnostic output is ON when there is a coil burnout or the sensing object is located in the unstable sensing area for 0.3 s or longer.	Prox.   Connect both the loads to the +V side of the control output and diagnostic output.

## **DC 3-Wire Models**

Operation mode	Output specifica- tions	Model	Timing Chart	Output circuit
NO	NPN output	E2E-X□E□ E2E-X□E□-M1	Sensing Present object Not present Operation ON indicator (red) OFF Control output (between brown and black leads) OFF Output voltage (between black and blue leads)	Proximity Sensor Current* Black Tr
NC	Ni N output	E2E-X□E□-M3	Sensing object Present Not present Operation indicator ON (red) Control output (between brown and black leads) Output voltage (between black and blue leads) Low	*Constant current output is 1.5 to 3 mA.  Note: For Connector Models, the connection between pins 1, 4 and 3 uses an NO contact, and the connection between pins 1, 2 and 3 uses an NC contact.
NO	DND	E2E-X□F□ E2E-X□F□-M1 E2E-X□F□-M3	Sensing object Present  Not present  Operation indicator (red) ON  Control output OFF  (Between blue and ON black leads) OFF  Output voltage (between brown and black leads) Low	Brown +V  Proximity Sensor main circuit  Load
NC	PNP output		Sensing object Present Not present Operation indicator (red) ON Control output (Between blue and black leads) OFF Output voltage (between brown and black leads) Low	*When a transistor is connected  Note: For Connector Models, the connection between pins 1, 4 and 3 uses an NO contact, and the connection between pins 1, 2 and 3 uses an NC contact.
AC 2-Wire N	lodels		**************************************	

## **AC 2-Wire Models**

Operation mode	Model	Timing Chart	Output circuit
NO	E2E-X□Y□ E2E-X□Y□-M1	Sensing Present object Not present  Operation ON indicator (red) OFF  Control output Reset	Proximity Sensor main circuit
NC		Sensing Present object Not present Operation ON indicator (red) OFF Control Operate output Reset	Note: For Connector Models, the connection between pins 3 and 4 uses an NO contact, and the connection between pins 1 and 2 uses an NC contact.

## **AC/DC 2-Wire Models**

Operation mode	Model	Timing Chart	Output circuit		
NO	E2E-X□T1	Non-sensing area  Unstable sensing area  Set position Stable sensing area  Proximity Sensor  Proximity Sensor  ON Setting indicator OFF (green) ON Operation OFF indicator (red) ON OFF Control output	Note: The load can be connected to either the +V or 0 V side.  There is no need to be concerned about the polarity (brown/blue) of the Proximity Sensor.		

Sensor I/O Connectors (Sockets on One Cable End)

Model for Connectors and Pre-wired Connectors: A Connector is not provided with the Sensor. Be sure to order a Connector separately. [Refer to Dimensions for the XS2, XS3, and XS5.]

Applicable			Connector		Applicable Proximity	Connection
connector			Cable length 2m	Cable length 5m	Sensor model	diagram
code	Screw	Appearance *1	CablConnector model number	CablConnector model number	number	No. *2
Α		Straight	XS2F-D421-DA0-F	XS2F-D421-GA0-F	FOE VDD1 M1C(I)	1
А		L-shape	XS2F-D422-DA0-F	XS2F-D422-GA0-F	E2E-X□D1-M1G(J)	ļ
В		Straight	XS2F-D421-DC0-F	XS2F-D421-GC0-F	E2E-X□E1-M1	10
Ь		L-shape	XS2F-D422-DC0-F	XS2F-D422-GC0-F	E2E-X□F1-M1	10
		Ctroight	XS2F-D421-DD0	XS2F-D421-GD0	E2E-X□D1-M1J-T	3
С		Straight	X52F-D421-DD0	X52F-D421-GD0	E2E-X□D1-M1	2
C		Labore	VCOE DAGO DDO	VC0E D400 CD0	E2E-X□D1-M1J-T	3
		L-shape	XS2F-D422-DD0	XS2F-D422-GD0	E2E-X□D1-M1	2
					E2E-X□D2-M1G(J)	6
					E2E-X□D2-M1J-T	8
		Straight	XS2F-D421-D80-F	XS2F-D421-G80-F	E2E-X□D2-M1	7
		Straight	A32F-D421-D00-F	A32F-D421-G00-F	E2E-X□D1S-M1 E2E-X□E2-M1 E2E-X□F2-M1 E2E-X□D2-M1G(J)	5
						11
D	M12				E2E-X□D2-M1G(J)	6
					E2E-X□D2-M1J-T	8
		Labora	XS2F-D422-D80-F	XS2F-D422-G80-F	E2E-X□D2-M1	7
		L-shape	A32F-D422-D00-F	A321 -D422-Q00-1	E2E-X□D1S-M1	5
					E2E-X□E2-M1 E2E-X□F2-M1	11
_		Straight	XS2F-A421-DB0-F	XS2F-A421-GB0-F	FOE VENA MA	4.4
Е		L-shape	XS2F-A422-DB0-F	XS2F-A422-GB0-F	E2E-X□Y1-M1	14
F		Straight	XS2F-A421-D90-F	XS2F-A421-G90-F	E2E-X□Y2-M1	15
		Smartclick Connector,	VCEE D404 D00 E	VCEE D401 C00 E	E2E-X D1-M1TGJ(-US)	16
G		Straight	XS5F-D421-D80-F	XS5F-D421-G80-F	E2E-X□D2-M1TGJ-US	17
Н		Smartclick Connector, Straight	XS5F-D421-D80-P XS5F-D421-G80-P	XS5F-D421-G80-P	E2E-X□D1-M1TGJ-U	18
		Oil-resistant Reinforced Cables			E2E-X□D2-M1TGJ-U	19
					E2E-X□D1-M3G	4
					E2E-X□D2-M3G	9
		Straight	XS3F-M421-402-A	XS3F-M421-405-A	E2E-X□E1-M3 E2E-X□F1-M3	12
	M8				E2E-X□E2-M3 E2E-X□F2-M3	13
1	IVIO				E2E-X□D1-M3G	4
					E2E-X□D2-M3G	9
		L-shape	XS3F-M422-402-A	XS3F-M422-405-A	E2E-X□E1-M3 E2E-X□F1-M3	12
					E2E-X□E2-M3 E2E-X□F2-M3	13

Note: Refer to Introduction to Sensor I/O Connectors/Sensor Controllers for details and for information on Cable length and Robotics Cables.

\*1. Images of straight and L-shaped connectors.









\*2. Refer to Connection Diagrams on page 23 for information on Proximity Sensor and I/O Connector connections.

## **Connections for Sensor I/O Connectors**

Connection	Proximity Sensor			Sensor I/O Connector				
diagram No.	Туре	Operation mode	Model	model number	Connections			
1	DC 2-wire (IEC pin wiring)		E2E-X□D1-M1G/M1GJ	T: Straight 2: L-shape XS2F-D42□-□A0-F □D: 2-m cable G: 5-m cable	E2E XS2F    O			
2	DC 2-wire (previous pin wiring)		E2E-X□D1-M1	T1: Straight 2: L-shape  XS2F-D42 - D0  D: 2-m cable G: 5-m cable	E2E XS2F			
3	DC 2-wire (no polarity)	NO	E2E-X□D1-M1J-T	T: Straight 2: L-shape XS2F-D42 - D0 D: 2-m cable G: 5-m cable	E2E XS2F			
4	DC 2-wire (M8 connector)		E2E-X□D1-M3G	T: Straight 2: L-shape XS3F-M42□-40□-A 2: 2-m cable 5: 5-m cable	E2E XS3F *  O Brown (+) O White (not connected) O Blue (not connected) O Black (-)			
5	DC 2-wire (diagnostic type)		E2E-X□D1S-M1	T1: Straight 2: L-shape XS2F-D42□-□80-F □: 2-m cable G: 5-m cable	E2E XS2F*  Brown (not connected)  White (diagnostic output) (+)  Blue (0 V)  Black (control output) (+)			
6	DC 2-wire (IEC pin wiring)		E2E-X□D2-M1G/M1GJ	1: Straight 2: L-shape  XS2F-D42 - 80-F  D: 2-m cable G: 5-m cable	E2E XS2F*  Shown (+)  White (-)  Blue (not connected)  Black (not connected)			
7	DC 2-wire (previous pin wiring)	NC NC	E2E-X□D2-M1	T1: Straight 2: L-shape XS2F-D42□-□80-F □ D: 2-m cable G: 5-m cable	E2E XS2F*  Brown (not connected)  White (+)  Blue (-)  Black (not connected)			
8	DC 2-wire (no polarity)	NO.	E2E-X□D2-M1J-T	T : Straight 2: L-shape  XS2F-D42 80-F  D: 2-m cable G: 5-m cable	E2E XS2F*  O Brown (+)(-) O White (-)(+) O Blue (not connected) O Black (not connected)			
9	DC 2-wire (M8 connector)		E2E-X□D2-M3G	1: Straight 2: L-shape  XS3F-M42 -40 - A  2: 2-m cable 5: 5-m cable	E2E XS3F*  O Brown (+) O White (-) O Blue (not connected) O Black (not connected)			

<sup>\*</sup> Different from Proximity Sensor wire colors.

Connection	Proximity Sensor			Sensor I/O Connector			
diagram No.	Туре	Operation mode	Model	model number	Connections		
10	DC 2 wire	NO	E2E-X□E/F1-M1	1: Straight 2: L-shape XS2F-D42□-□C0-F □D: 2-m cable G: 5-m cable	E2E XS2F  Brown (+V)  Blue (0 V)  Black (output)		
11	DC 3-wire	NC	E2E-X□E2/F2-M1	1: Straight 2: L-shape XS2F-D42 - 80-F D: 2-m cable G: 5-m cable	E2E XS2F  O Brown (+V) O White (output) O Blue (0 V) O Black (not connected)		
12	DC 3-wire	NO	E2E-X□E1/F1-M3	1: Straight 2: L-shape  XS3F-M42 -40 -A  2: 2-m cable 5: 5-m cable	E2E XS3F  White (not connected)  Blue (0 V)  Black (output)		
13	(M8 connector)	NC	E2E-X□E2/F2-M3	1: Straight 2: L-shape  XS3F-M42 -40 -A  2: 2-m cable 5: 5-m cable	E2E XS3F  O Brown (+V) O White (output) O Blue (0 V) O Black (not connected)		
14	AC 2-wire	NO	E2E-X□Y1-M1	1: Straight 2: L-shape  XS2F-A42 B0-F	E2E XS2F  O O O O O O O O O O O O O O O O O O O		
15	AO 2-WIIE	NC	E2E-X□Y2-M1	XS2F-A421-□90-F D: 2-m cable G: 5-m cable	E2E X\$2F*  O Brown O White O Blue (not connected) O Black (not connected)		
16		NO	E2E-X□D1- M1TGJ(-US)	XS5F-D421-□80-F D: 2-m cable G: 5-m cable	E2E XSSF  O Brown (+) O White (not connected) O Blue (not connected) O Black (-)		
17	DC 2-wire - (Smartclick connector)	NC	E2E-X□D2- M1TGJ-US	XS5F-D421-□80-F D: 2-m cable G: 5-m cable	E2E XSSF  O Brown (+) O White (-) O Blue (not connected) O Black (not connected)		
18		NO	E2E-X□D1- M1TGJ-U	XS5F-D421-□80-P D: 2-m cable G: 5-m cable	E2E XSSF  O Brown (+) O White (not connected) O Blue (not connected) O Black (-)		
19		NC	E2E-X□D2- M1TGJ-U	XS5F-D421-□80-P D: 2-m cable G: 5-m cable	E2E XSSF		

<sup>\*</sup> Different from Proximity Sensor wire colors.

Refer to Introduction to Sensor I/O Connectors/Sensor Controllers for details.

## **Safety Precautions**

## Refer to Warranty and Limitations of Liability.



This product is not designed or rated for ensuring safety of persons either directly or indirectly. Do not use it for such purposes.



#### **CAUTION**

- Do not short the load. Explosion or burning may
  result
- Do not supply power to the Sensor with no load, otherwise Sensor may be damaged.


#### **Precautions for Correct Use**

Do not use this product under ambient conditions that exceed the ratings.

#### Design

#### **Influence of Surrounding Metal**

When mounting the Sensor within a metal panel, ensure that the clearances given in the following table are maintained. Failure to maintain these distances may cause deterioration in the performance of the Sensor.



## **Influence of Surrounding Metal**

(Unit: mm)


Model	Item	М8	M12	M18	M30		
		ı	0				
		d	8	12	18	30	
	Shielded	D /	$\gamma_1$	0	1873		
DC 2-Wire Models		m	4.5	8	20	40	
E2E-X□D□		n	12	18	27	45	
AC/DC 2-Wire Models		P	12	15	22	30	
E2E-X□T1		d	24	40	70	90	
	Unshielded	D	12	15	22	30	
		m	8	20	40	70	
		n	24	40	70	90	
		I	0				
		d	8	12	18	30	
	Shielded	D	0				
DC 3-Wire Models E2E-X□E□		m	4.5	8	20	40	
E2E-X□F□		n	12	18	27	45	
AC 2-Wire Models		I	6	15	22	30	
E2E-X Y		d	24	40	55	90	
	Unshielded	D	6	15	22	30	
		m	8	20	40	70	
		n	24	36	54	90	

## **Relationship between Sizes and Models**

		Model	Model
			E2E-X2D□
		Shielded	E2E-X1R5E□
		Sillelueu	E2E-X1R5F□
	M8		E2E-X1R5Y□
	IVIO		E2E-X4MD□
		Unshielded	E2E-X2ME□
,		Orisilielded	E2E-X2MF□
	33		E2E-X2MY□
Ì,	10		E2E-X3D□
			E2E-X2E□
		Shielded	E2E-X2F□
			E2E-X2Y□
	M12		E2E-X3T1
			E2E-X8MD□
		Unshielded	E2E-X5ME□
		Orisiliciaca	E2E-X5MF□
			E2E-X5MY□
			E2E-X7D□
			E2E-X5E□
		Shielded	E2E-X5F□
			E2E-X5Y□
	M18		E2E-X7T1
			E2E-X14MD□
		Unshielded	E2E-X10ME□
		Onomorada	E2E-X10MF□
			E2E-X10MY□
			E2E-X10D□
			E2E-X10E□
		Shielded	E2E-X10F□
			E2E-X10Y□
	M30		E2E-X10T1
			E2E-X20MD□
		Unshielded	E2E-X18ME□
		2	E2E-X18MF□
			E2E-X18MY□

#### **Mutual Interference**

When installing Sensors face-to-face or side-by-side, ensure that the minimum distances given in the following table are maintained.





#### **Mutual Interference**

(Unit: mm)

Model		Item	М8	M12	M18	M30
DC 2-Wire Models	Object of	Α	20	30 (20)	50 (30)	100 (50)
E2E-X□D□	Shielded	В	15	20 (12) *	35 (18) *	70 (35)
AC/DC 2-Wire Models	Unshielded	Α	80	120 (60)	200 (100)	300 (100)
E2E-X□T1	Orishleided	В	60	100 (50)	110 (60)	200 (100)
DC 3-Wire Models	Shielded	Α	20	30 (20)	50 (30)	100 (50)
E2E-X□E□/X□F□	Shleided	В	15	20 (12) *	35 (18) *	70 (35)
AC 2-Wire Models	Unshielded	Α	80	120 (60)	200 (100)	300 (100)
E2E-X□Y□	Orisinelaea	В	60	100 (50)	110 (60)	200 (100)

Note: Values in parentheses apply to Sensors operating at different frequencies.

#### **Loads with Large Surge Currents (E2E-X**□**T**□)

If a load with a large surge current is connected, such as a relay, lamp, or motor, the surge current may cause the load short-circuit protection circuit to operate, resulting in operating errors.


#### Mounting

#### **Tightening Force**

Do not tighten the nut with excessive force. A washer must be used with the nut.







Part B Part A

Note: 1. The allowable tightening strength depends on the distance from the edge of the head, as shown in the following table. (A is the distance from the edge of the head. B includes the nut on the head side. If the edge of the nut is in part A, the tightening torque for part A applies instead.)

2. The following strengths assume washers are being used.

Model		Par	Part B		
		Dimension	Torque	Torque	
M8	Shielded	9	9 N·m	12 N·m	
IVIO	Unshielded	3	9 14-111	12 11111	
M12			30 N·m		
M18		70 N·m			
M30		180 N·m			

## Connecting a DC 2-Wire Proximity Sensor to a PLC (Programmable Controller)

#### **Required Conditions**

Connection to a PLC is possible if the specifications of the PLC and the Proximity Sensor satisfy the following conditions. (The meanings of the symbols are given at the right.)

 The ON voltage of the PLC and the residual voltage of the Proximity Sensor must satisfy the following.

 $V_{\text{ON}} \leq V_{\text{CC}} - V_{\text{R}}$ 

2. The OFF current of the PLC and the leakage current of the Proximity Sensor must satisfy the following.

 $\mathsf{IOFF} \geq \mathsf{I}_{\mathsf{leak}}$ 

(If the OFF current is not listed in the PLC's input specifications, take it to be 1.3 mA.)

 The ON current of the PLC and the control output of the Proximity Sensor must satisfy the following.

lout (min.)  $\leq$  lon  $\leq$  lout (max.)

The ON current of the PLC will vary, however, with the power supply voltage and the input impedance, as shown in the following equation.

$$Ion = (Vcc - V_R - V_{PC}) / R_{IN}$$

#### Example

In this example, the above conditions are checked when the Proximity Sensor is the E2E-X7D1-N and the power supply voltage is 24 V.

- 1. Von (14.4 V)  $\leq$  Vcc (20.4 V) Vr (3 V) = 17.4 V: OK
- 2. Ioff (1.3 mA)  $\geq$  Ileak (0.8 mA): OK
- 3. Ion = [Vcc (20.4 V) V<sub>R</sub> (3 V)  $\underline{\text{VPc}}$  (4 V)] / R<sub>IN</sub> (3 k $\Omega$ ) = Approx. 4.5 mA

Therefore, lout (min.) (3 mA)  $\leq$  lon (4.5 mA): OK Connection is thus possible.

#### **Connection Example (Reference)**

PLC	Von: ON voltage (14.4 V) Ion: ON current (typically 7 mA) Ior: OFF current (1.3 mA) Rin: Input impedance (3 kΩ) VPC: Internal residual voltage (4 V)
Proximity Sensor	Vn: Output residual voltage (3 V) Ileak: Leakage current (0.8 mA) Iouт: Control output (3 to 100 mA) Vcc: Power supply voltage (PLC: 20.4 to 26.4 V)

<sup>\*</sup> Mutual interference will not occur for close-proximity mounting if models with different frequencies are used together.

## **Dimensions**

## **Main Units**

## **Model Number-Dimensions Drawing Number Lookup Table**

		Model	DC 2-Wire Models		DC 3-Wire Models		AC 2-Wire Models		AC/DC 2-Wire Mo	dels
Model	Shield	ed	Model	No.	Model	No.	Model	No.	Model	No
		M8	E2E-X2D□(-US)	1	E2E-X1R5E□/F□	1	E2E-X1R5Y□	3		·
	Shielded	M12	E2E-X3D□(-US)	5	E2E-X2E□/F□	5	E2E-X2Y□	7	E2E-X3T1	9
	Sillelueu	M18	E2E-X7D□(-US)	10	E2E-X5E□/F□	10	E2E-X5Y□	10	E2E-X7T1	10
Pre-wired Models		M30	E2E-X10D□(-US)	12	E2E-X10E□/F□	12	E2E-X10Y□	12	E2E-X10T1	12
Pre-wired Models		M8	E2E-X4MD□(-US)	2	E2E-X2ME□/F□	2	E2E-X2MY□	4		
	Unshielded	M12	E2E-X8MD□(-US)	6	E2E-X5ME□/F□	6	E2E-X5MY□	8		
	Unsnielded	M18	E2E-X14MD□(-US)	11	E2E-X10ME□/F□	11	E2E-X10MY□	11		
		M30	E2E-X20MD□(-US)	13	E2E-X18ME□/F□	13	E2E-X18MY□	13	=	
		M8	E2E-X2D□-M1(G)	14	E2E-X1R5E/F□-M1	14				
	01:-1-11	M12	E2E-X3D□-M1(G)	16	E2E-X2E/F□-M1	16	E2E-X2Y□-M1	18	=	
	Shielded	M18	E2E-X7D□-M1(G)	20	E2E-X5E/F□-M1	20	E2E-X5Y□-M1	20		
Connector		M30	E2E-X10D□-M1(G)	22	E2E-X10E/F□-M1	22	E2E-X10Y□-M1	22	-	
Models (M12)		M8	E2E-X4MD□-M1(G)	15	E2E-X2ME/F□-M1	15				
( = /		M12	E2E-X8MD□-M1(G)	17	E2E-X5ME/F□-M1	17	E2E-X5MY□-M1	19	-	
	Unshielded	M18	E2E-X14MD□-M1(G)	21	E2E-X10ME/F□-M1	21	E2E-X10MY□-M1	21		
		M30	E2E-X20MD□-M1(G)	23	E2E-X18ME/F□-M1	23	E2E-X18MY□-M1	23	-	
Connector	Shielded		E2E-X2D□-M3G		E2E-X1R5E/F□-M3	24				
Models (M8)	Unshielded	M8	E2E-X4MD□-M3G	25	E2E-X2ME/F□-M3	25				
			E2E-X2D□-M1(T)GJ(-U)				0			
		M8 E2E-X2D□-M1TGJ-US	26							
		M12	E2E-X3D□-M1(T)GJ(-U)	07			<b>√</b> ∕∞.			
			E2E-X3D□-M1TGJ-US	27			TV N			
	Shielded		E2E-X7D□-M1(T)GJ(-U)	-00			Gr. Op			
		M18	E2E-X7D□-M1TGJ-US	28		J. 18	100			
Pre-wired			E2E-X10D□-M1(T)GJ(-U)	-00		R.S	P. S. C.			
Connector		M30	E2E-X10D□-M1TGJ-US	29	1 1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1					
Models		M8	E2E-X4MD□-M1TGJ-US	30	17.18	0				
		MAG	E2E-X8MD1-M1(T)GJ	04	800 35					
		M12	E2E-X8MD□-M1TGJ-US	31	10 31					
	Unshielded		E2E-X14MD1-M1(T)GJ	-00	, **					
		M18	E2E-X14MD□-M1TGJ-US	32	May "					
			E2E-X20MD1-M1(T)GJ	-00						
		M30	E2E-X20MD□-M1TGJ-US	33						
Pre-wired		M12	E2E-X3D1-M1J-T	27						
Connector Models	Shielded	M18	E2E-X7D□-M1J-T	28	<del></del>					
(no polarity)		M30	E2E-X10D□-M1J-T	29	=					

Note 1. Two clamping nuts and one toothed washer are provided with M8 to M30 Models.


2. The model numbers of M8 to M30 Pre-wired Models are laser-marked on the milled section and cable section. This does not apply, however, to models that end in -U.

#### **Pre-wired Models (Shielded)**



# **Pre-wired Models (Unshielded)**


#### E2E-X2D Diagram 1



- 10.4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m 4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m Robotics Cable Models: 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m 4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m Models with Highly Oli-resistant Cables: 4-dia. polyurethane-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m The cable can be extended up to 200 m (separate metal conduit).

  \*\*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)


#### E2E-X4MD Diagram 2



- \*1. 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m
  4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter:
- 1.3 mm), Standard length: 2 m Robotics Cable Models:


- Robotics Cable Models:
  4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter:
  1.27 mm), Standard length: 2 m
  4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter:
  1.27 mm), Standard length: 2 m
  The cable can be extended up to 200 m (separate metal conduit).
  \*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

#### Diagram 3 E2E-X1R5Y




4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m The cable can be extended up to 200 m (separate washer

#### Diagram 4 E2E-X2MY



Two clamping nuts thed 4-dia. vinyl-insulated round cable with 2 conductors Toothed (Conductor cross section: 0.3 mm², Insulator diameter: washer 1.3 mm), Standard length: 2 m The cable can be extended up to 200 m (separate metal conduit)

#### Diagram 5 E2E-X3D



\*1. 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m 4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m Robotics Cable Models:

metal conduit).

4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm<sup>2</sup>. Insulator diameter:

1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m


1.2/ mm), Standard length: 2 m Models with Highly Oil-resistant Cables: 4-dia, polyurethane-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m

The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for

the diagnostic output.


\*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

#### Diagram 6 E2E-X8MD




- \*1. 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm2, Insulator diameter:
- \*1.4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm²·l Insulator diameter: 1.3 mm), Standard length: 2 m
  4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m
  Robotics Cable Models:
  4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
  4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
  The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.
  \*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

#### E2E-X2Y Diagram 7



#### Diagram 8 E2E-X5MY



#### **Mounting Hole Dimensions**




Dimension	M8	M12
F (mm)	8.5 <sup>+0.5</sup> dia.	12.5 <sup>+0.5</sup> dia.

#### **Pre-wired Models (Shielded)**

#### **Pre-wired Models (Unshielded)**




#### **E2E-X3T1** Diagram 9



14-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m The cable can be extended up to 200 m (separate metal conduit)

\*2 Operation indicator (red), Setting indicator (green)

#### Diagram 10 E2E-X7D□/E2E-X5E□/F□ E2E-X5Y\(\subseteq\)/E2E-X7T1



\*1. 6-dia, vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm²,

Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m Robotics Cable Models:

Additional conditions and the conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm²,

Insulator diameter: 1.74 mm), Standard length: 2 m Models with Highly Oil-resistant Cables: 6-dia. polyurethane-insulated round cable with 2 conductors (Conductor cross section:

o-dia. polyprientaire-insulated round cable with z conductors (conductor cross section. 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m


The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.

\*2. D1/T Models: Operation indicator (red), Setting indicator (green)

D2/E/F/Y Models: Operation indicator (red)

Diagram 11 E2E-X14MD□/E2E-X10ME□/F□

E2E-X10MY




6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm²,

Insulator diameter: 1.9 mm), Standard length: 2 m Robotics Cable Models: 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm²,

Insulator diameter: 1.74 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m The cable can be extended (separate metal conduit) up to 200 m for the control output

and up to 100 m for the diagnostic output.
D1/T Models: Operation indicator (red), Setting indicator (green)
D2/E/F/Y Models: Operation indicator (red)

#### Diagram 12 E2E-X10D /E2E-X10E /F E2E-X10Y / E2E-X10T1



\*1. 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m

section: 0.5 mm\*, insulator diameter: 1.9 mm), Standard lengtn: 2 m

Robotics Cable Models:
6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm\*, insulator diameter: 1.74 mm), Standard length: 2 m


6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm\*, Insulator diameter: 1.74 mm), Standard length: 2 m

Models with Highly Oil-resistant:
6-dia-polyurathapa insulated round cable with 2 conductors (Conductor Conductors)

Models With Highly Oll-resistant:
6-dia, polyuerthane-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m
The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.

\*2. D1/T Models: Operation indicator (red), Setting indicator (green)
D2/E/F/Y Models: Operation indicator (red)

#### Diagram 13 E2E-X20MD /E2E-X18ME /F E2E-X18MY



\*1.6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m
6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross

6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m Robotics Cable Models:
6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m
6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m
The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.

\*2. D1/T Models: Operation indicator (red), Setting indicator (green)
D2/E/F/Y Models: Operation indicator (red)

#### **Mounting Hole Dimensions**



Dimension	M12	M18	M30
F (mm)	12.5 <sup>+0.5</sup> dia.	18.5 <sup>+0.5</sup> dia.	30.5 <sup>+0.5</sup> dia.

## **M8 Connector Models**

(Shielded)




#### **M8 Connector Models** (Unshielded)




#### Diagram 24 E2E-X2D□-M3G/E2E-X1R5E□-M3/X1RF□-M3

15 dia.



## Diagram 25 E2E-X4MD□-M3G/E2E-X2ME□-M3/X2MF□-M3



#### **M12 Connector Models** (Shielded)




**M12 Connector Models** (Unshielded)



#### Diagram 14 E2E-X2D□-M1(G) **E2E-X1R5E** -M1/**E2E-X1R5F** -M1





Setting indicator (green) D2/E/F Models: Operation indicator (red)

#### Diagram 15 E2E-X4MD□-M1(G) E2E-X2ME -M1/E2E-X2MF -M1






\* D1 Models: Operation indicator (red), Setting indicator (green)
D2/E/F Models: Operation indicator (red)

#### Diagram 16 E2E-X3D□-M1(G) E2E-X2E - M1/E2E-X2F - M1






\* D1 Models: Operation indicator (red). Setting indicator (green) D2/E/F Models: Operation indicator (red)

#### Diagram 17 E2E-X8MD□-M1(G) E2E-X5ME -M1/E2E-X5MF -M1







\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/F Models: Operation indicator (red)

#### Diagram 18 E2E-X2Y□-M1







#### Diagram 19 E2E-X5MY□-M1



# Diagram 20 E2E-X7D□-M1(G)/E2E-X5E□-M1/X5F□-M1 E2E-X5Y□-M1



# Diagram 22 E2E-X10D $\square$ -M1(G)/E2E-X10E $\square$ -M1/X10F $\square$ -M1 E2E-X10Y $\square$ -M1



D1 Models: Operation indicator (red), Setting indicator (green)
 D2/E/Y Models: Operation indicator (red)

#### 





Diagram 23 E2E-X20MD□-M1(G)/E2E-X18ME□-M1/ X18MF□-M1 E2E-X18MY□-M1



#### **Mounting Hole Dimensions**




40			
100 A 700 A 100 A	18	M30	
<sup>.5</sup> dia. 18.5 <sup>+0</sup>	<sup>.5</sup> dia.	30.5+0.5	dia.
10/17			
	100 A 700 A 100 A	100 A 700 A 700 A	0.5 dia. 18.5+0.5 dia. 30.5+0.5

#### **Pre-wired Connector Models (Shielded)**



Diagram 26 E2E-X2D□-M1TGJ-U \*3 E2E-X2D1-M1TGJ E2E-X2D -M1TGJ-US





- Standard length: 300 mm

  2. D1 Models: Operation indicator (red), Setting indicator (green)
  D2 Models: Operation indicator (red)

  \*3. The connectors for M1TGJ models are XS5 Smartclick connectors.

Diagram 27 E2E-X3D□-M1GJ

E2E-X3D1-M1J-T

E2E-X3D -M1TGJ-U \*3

E2E-X3D1-M1TGJ E2E-X3D□-M1TGJ-US







Diagram 28 E2E-X7D□-M1GJ


E2E-X7D -M1J-T

E2E-X7D -M1TGJ-U \*3

E2E-X7D1-M1TGJ

E2E-X7D□-M1TGJ-US





- \*12. \*1. No U suffix: 6-dia. Vinyl-insulated round cable
  U suffix: 6-dia. Polyurethane insulated round cable,
  Standard length: 300 mm
  \*2. D1 Models: Operation indicator (red), Setting indicator (green)
  D2 Models: Operation indicator (red)
  \*3. The connectors for M1TGJ models are XS5 Smartclick connectors.


Diagram 29 E2E-X10D□-M1GJ


E2E-X10D□-M1J-T

E2E-X10D -M1TGJ-U \*3

E2E-X10D1-M1TGJ

E2E-X10D□-M1TGJ-US





Toothed washer

- 2

  1. No U suffix: 6-dia. Vinyl-insulated round cable
  U suffix: 6-dia. Polyurethane insulated round cable,
  Standard length: 300 mm

  2. D1 Models: Operation indicator (red), Setting indicator (green)
  D2 Models: Operation indicator (red)

  3. The connectors for M1TGJ models are XSS Smartclick connectors.

#### **Pre-wired Connector Models (Unshielded)**

## Diagram 30 E2E-X4MD□-M1TGJ-US






Diagram 31 E2E-X8MD1-M1GJ E2E-X8MD1-M1TGJ E2E-X8MD□-M1TGJ-US






Diagram 32 E2E-X14MD□-M1GJ E2E-X14MD1-M1TGJ E2E-X14MD□-M1TGJ-US








Diagram 33 E2E-X20MD1-M1GJ E2E-X20MD1-M1TGJ E2E-X20MD□-M1TGJ-US





## **Mounting Hole Dimensions**



Dimension	M8	M12	M18	M30	
F (mm)	8.5 <sup>+0.5</sup> dia.	12.5 <sup>+0.5</sup> dia.	18.5 <sup>+0.5</sup> dia.	30.5 <sup>+0.5</sup> dia.	

## **Dimensions for Proximity Sensors with Sensor I/O Connectors**


#### **Shielded Models**


Straight Connectors

#### **Unshielded Models**

# Straight Connectors

L-shape Connectors L-shape Connector





## **Dimensions with the XS2F/XS5F Connected** (Unit: mm)

Dimension Sensor diameter		L1	L2
M8		Approx. 75	Approx. 62
M12*	DC	Approx. 80	Approx. 67
	AC	Approx. 85	Approx. 72
M18	·	Approx. 85	Approx. 72
M30		Approx. 90	Approx. 77

<sup>\*</sup>The overall length of the Sensor is different between AC and DC Models for Sensors with diameters of M12. This will change the dimension when the I/O Connector is connected.

## Dimensions with the XS3F Connected (Unit: mm)

Dimension Sensor diameter	L1	L2
M8	Approx. 65	Approx. 54

## **Accessories (Order Separately)**

## **Sensor I/O Connectors**

Refer to Introduction to Sensor I/O Connectors/Sensor Controllers for details.

**Mounting Brackets** 

**Protective Covers** 

**Sputter Protective Covers** 

Refer to Y92 ☐ for details.

#### Terms and Conditions Agreement

#### Read and understand this catalog.

Please read and understand this catalog before purchasing the products. Please consult your OMRON representative if you have any questions or comments.

#### Warranties.

- (a) Exclusive Warranty. Omron's exclusive warranty is that the Products will be free from defects in materials and workmanship for a period of twelve months from the date of sale by Omron (or such other period expressed in writing by Omron). Omron disclaims all other warranties, express or implied.
- (b) Limitations. OMRON MAKES NO WARRANTY OR REPRESENTATION, EXPRESS OR IMPLIED, ABOUT NON-INFRINGEMENT, MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OF THE PRODUCTS. BUYER ACKNOWLEDGES THAT IT ALONE HAS DETERMINED THAT THE

PRODUCTS WILL SUITABLY MEET THE REQUIREMENTS OF THEIR INTENDED USE.

Omron further disclaims all warranties and responsibility of any type for claims or expenses based on infringement by the Products or otherwise of any intellectual property right. (c) Buyer Remedy. Omron's sole obligation hereunder shall be, at Omron's election, to (i) replace (in the form originally shipped with Buyer responsible for labor charges for removal or replacement thereof) the non-complying Product, (ii) repair the non-complying Product, or (iii) repay or credit Buyer an amount equal to the purchase price of the non-complying Product; provided that in no event shall Omron be responsible for warranty, repair, indemnity or any other claims or expenses regarding the Products unless Omron's analysis confirms that the Products were properly handled, stored, installed and maintained and not subject to contamination, abuse, misuse or inappropriate modification. Return of any Products by Buyer must be approved in writing by Omron before shipment. Omron Companies shall not be liable for the suitability or unsuitability or the results from the use of Products in combination with any electrical or electronic components, circuits, system assemblies or any other materials or substances or environments. Any advice, recommendations or information given orally or in writing, are not to be construed as an amendment or addition to the above warrantv.

See <a href="http://www.omron.com/global/">http://www.omron.com/global/</a> or contact your Omron representative for published information.

#### Limitation on Liability; Etc.

OMRON COMPANIES SHALL NOT BE LIABLE FOR SPECIAL, INDIRECT, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, LOSS OF PROFITS OR PRODUCTION OR COMMERCIAL LOSS IN ANY WAY CONNECTED WITH THE PRODUCTS, WHETHER SUCH CLAIM IS BASED IN CONTRACT, WARRANTY, NEGLIGENCE OR STRICT LIABILITY.

Further, in no event shall liability of Omron Companies exceed the individual price of the Product on which liability is asserted.

#### Suitability of Use.

Omron Companies shall not be responsible for conformity with any standards, codes or regulations which apply to the combination of the Product in the Buyer's application or use of the Product. At Buyer's request, Omron will provide applicable third party certification documents identifying ratings and limitations of use which apply to the Product. This information by itself is not sufficient for a complete determination of the suitability of the Product in combination with the end product, machine, system, or other application or use. Buyer shall be solely responsible for determining appropriateness of the particular Product with respect to Buyer's application, product or system. Buyer shall take application responsibility in all cases.

NEVER USE THE PRODUCT FOR AN APPLICATION INVOLVING SERIOUS RISK TO LIFE OR PROPERTY OR IN LARGE QUANTITIES WITHOUT ENSURING THAT THE SYSTEM AS A WHOLE HAS BEEN DESIGNED TO ADDRESS THE RISKS, AND THAT THE OMRON PRODUCT(S) IS PROPERLY RATED AND INSTALLED FOR THE INTENDED USE WITHIN THE OVERALL EQUIPMENT OR SYSTEM.

#### Programmable Products.

Omron Companies shall not be responsible for the user's programming of a programmable Product, or any consequence thereof.

#### Performance Data.

Data presented in Omron Company websites, catalogs and other materials is provided as a guide for the user in determining suitability and does not constitute a warranty. It may represent the result of Omron's test conditions, and the user must correlate it to actual application requirements. Actual performance is subject to the Omron's Warranty and Limitations of Liability.

#### Change in Specifications.

Product specifications and accessories may be changed at any time based on improvements and other reasons. It is our practice to change part numbers when published ratings or features are changed, or when significant construction changes are made. However, some specifications of the Product may be changed without any notice. When in doubt, special part numbers may be assigned to fix or establish key specifications for your application. Please consult with your Omron's representative at any time to confirm actual specifications of purchased Product.

Errors and Omissions. Information presented by Omron Companies has been checked and is believed to be accurate; however, no responsibility is assumed for clerical, typographical or proofreading errors or omissions.

2020.4

In the interest of product improvement, specifications are subject to change without notice.

